


Leader Rig - Installation & Pre-Augering with Silent Piler



Project Location	Upminster Cemetery Extension - Phase 1
Contract E Number	E4352A
Type of Project	Cemetery Extension - water cut off cofferdam
Client	Birse Civils on behalf of Havering Borough Council
Duration of Work	5 Weeks
Piling Works	July 2013 - August 2013
Purpose of Piling	Permanent cofferdam for water cut off
Type of Pile	AZ18-700 Steel Sheet Pile, in Jagged Wall profile & PU18, (Silent Piler); L= 8.0 — 8.5m
Piling System	ABI 13/16 Leader - Rig Pre-Augering & Vibro-installation. Silent Piler used near to existing Cemetery
Particulars	Pre-Augering works carried out for the Silent Piling works. Vibro Installation & Drop Hammer Back driving on remainder. Special sealant, (Roxan) used in clutches to ensure watertightness.

Borehole Information



Sheet Piling, Construction
& Professional Design
Services

Unit 7,
The Oaks Business Village
Revenge Road,
Lordswood,
Kent,
ME5 8LF

TEL: 01622 794460
Enquiries@berryrange.com
www.berryrange.com

