


Conventional pile installation with Crane suspended vibro-hammer



Borehole Information

SPT Values



Project Location	Heybridge Basin, Maldon
Contract E Number	E6143A
Type of Project	Installation of New Lock Gates
Client	Anglian Land Drainage
Duration of Work	1 Week
Piling Works	October 2016
Purpose of Piling	Temporary Cut off wall to install new lock gates
Type of Pile	TKL 605 x 9.0m long
Piling Machine	Crane Suspended Vibratory Hammer
Particulars	Conventional Piling used for installation works. Extraction was carried out with the WP150 Silent Piler.



Sheet Piling, Construction & Professional Design Services

Unit 7,
The Oaks Business Village
Revenge Road,
Lordswood,
Kent,
ME5 8LF

TEL: 01622 794460
Enquiries@berryrange.com
www.berryrange.com

